Bonds:- Bond all brick work throughout with true headers every fifth course, lapped through the wall in every case.

Cutting and Patching:- Contractor to do all cutting and patching of masonry walls required in connection with service system contractors.

Setting Steel Works Anchors, Etc.:- The contractor to set all steel lintels over windows and doors, and other openings; also, jambs and any other iron work coming in contact with the brick work.

At the proper heights and locations, set all bearing plates for carrying structural steel, lintels, beams and other steel framing and securely anchor same.

All steel construction to be properly anchored and all frames and other metal work built into the brick walls, to be set true, plumb and braced before proceeding with the brick work.

The contractor to build in all anchors and tie rods required by service system contractors, and others.

Setting Window Frames:- All single unit window frames to be set in brick work as brick work is carried up. If multiple unit frames are not set as brick work is carried up, provision is to be made for installing them later, as approved by the Consulting Engineer.

Grounds, bucks and other similar construction to be securely bolted or attached to walls in manner to be approved.